



**GILA COUNTY
COPPER ADMINISTRATION BUILDING
DEDICATED FIRE LINE AND FIRE HYDRANT
INFORMAL BID REQUEST NO. 031015IBR**

ADDENDUM #1:
DATE: 3/18/2015

CLARIFICATIONS:

1. Sign-In Sheet from Pre-Bid Walk-thru / Meeting is attached.
2. Contractor will perform pressure test per MAG Spec 610.15 and disinfect per City of Globe requirements.
3. Contractor is responsible for ensuring that all utilities have been located prior to commencement of work.
4. Pipe bedding per Mag Spec 601.4.2 shall be required. Trenches shall be backfilled in lifts no greater than 12 inches and compacted to 90%. The Contractor is not required to provide compaction testing. Gila County will thoroughly inspect all backfill and provide their own compaction testing at their discretion.
5. Thrust block per Mag Spec 610.14 shall be used.
6. Permits will not be required from either City of Globe or Gila County. Prior to backfill all joints and connections must be made available for inspection by Gila County and City of Globe with a minimum of 24 hours' notice.
7. Substitute C900 pipe material for Ductile Iron Pipe with polywrap per Mag Spec 610 & 750.2
8. On top of the hill the waterline shall have 5 ft. of cover. After the final site grading it is anticipated the water line will have 4 ft. of cover. The fire hydrant shall be set in anticipation of 4 ft. of cover over the water line.
9. The Contractor shall also install two (2) – 1 ½ conduits common trench with the waterline. The conduits can have minimum separation and will need to be stubbed up out of the ground near the new fire hydrant on top and near the gate down below.

**This concludes Addendum No. 1 to Invitation for Bids No. 031015IBR
Bid date and time remain the same.**

